

Americans with Disabilities Act (ADA) Information

If you would like copies of this document in an alternative format - large print, Braille, cassette tape, or on computer disk, please call Washington State Telecommunications Relay Service TT 1-800-833-6388, Tele-Braille 1-800-833-6385, Voice 1-800-833-6384, and ask to be connected to (360) 705-7097.

Individuals requiring reasonable accommodation may request written materials in alternate formats, sign language interpreters, physical accessibility accommodations, or other reasonable accommodation by contacting the event sponsor Ken Walker 360-705-7017, usually 2 weeks before the bid opening. Persons with hearing impairments may call Washington State Telecommunications Relay Service TT 1-800-833-6388 Tele-Braille 1-800-833-6385, Voice 1-800-833-6384, and ask to be connected to the event sponsor's phone number.

(THURSTON) **YELM LOOP STAGE 1** (CL 1 or 4, \$7,500,000 - \$10,000,000) **CONTAINS APPRENTICE UTILIZATION REQUIREMENT: 15%**. Requires: Constructing a roundabout and new highway alignment with bike and pedestrian paths. The work includes clearing and grubbing, grading, drainage, surfacing, paving with hot mix asphalt, illumination systems, pavement markings, roadside seeding and planting, permanent signing traffic control and other work. 125 Working days. Involves 138 items. 73200 CY rdwy excav incl haul, 24800 CY embank comp, 498 LF sch A culv pipe, 32 EA catch basin, 924 LF CL V reinf storm sewer pipe, 2111 LF st casing, 50 CY conc CL 4000, 25210 T crushed surface base course, 1570 SY plane bit pvmt, 26200 T HMA CL 1/2 IN PG 64-22, 12450 SY soil residual herbicide, 6120 LF silt fence, 16 ACRE seed, fert, mulch, 10990 CY topsoil, 23 EA garry oak, 361 EA blue oat grass, 342 EA tall oregon grape, 588 EA black-eyed susan, 8182 EA fescue, 6900 CY fine compost, 117 T boulders, 310 CY river cobbles, 2842 LF cement conc traffic curb and gutter, 1863 LF cement conc traffic curb, 3316 SF conc for pigmented truck apron, 36750 LF paint line, 2820 LF plastic wide line, 4540 CY struct excav CL B incl haul, 29110 SF shoring or extra excav CL B, 2780 SY cement conc sidewalk, 2055 SF stamped conc, 28 EA cement conc sidewalk ramp, 17090 LF coated chain link fence, 168 SF detectable warning pattern. **CONTAINS MINIMUM BID ITEM: TYPE B PROGRESS SCH.** Lump Sum Bids for: Perm signing, city entrance marker, illum sys, temp traffic control, clean exist drain struct, SPCC plan.